

WYKAZ ZJAZDÓW GOSPODARCZYCH I NA DROGI BOCZNE

na drodze powiatowej nr 1962B Kownaty - Guty
nr 1924B Guty - Olszyny
nr 1964B Olszyny - Bożejewo

Lp	Lokalizacja	Strona	Nr działki	Typ katal. wg KPED	Objętość robót m3	Powierzch. naw. bitum. m2	Powierzch. naw. żwirow. m2	Średnica rur m	Długość rur mb
1	2	3	4	5	6	7	8,0	9	10
1	0+082	L	465	03.82	2,20	-	25,7	-	-
2	0+086	P	537	03.82	3,10	-	25,7	-	-
3	0+112	P	536	03.82	2,60	-	25,7	-	-
4	0+134	L	462/3	03.82	3,20	-	25,7	-	-
5	0+145	P	535	03.82	2,20	-	25,7	-	-
6	0+158	L	461	03.82	2,80	-	25,7	-	-
7	0+184	L	459	03.82	2,50	-	25,7	-	-
8	0+198,50	L	459	03.82	2,70	-	25,7	-	-
9	0+224	P	530	03.82	3,10	-	25,7	-	-
10	0+227	L	547	03.82	3,40	-	25,7	-	-
11	0+248	L	456	03.82	1,60	-	25,7	-	-
12	0+268	L	455	03.82	1,40	-	25,7	-	-
13	0+287	P	528/1	03.82	9,80	-	25,7	-	-
14	0+308	L	451	03.82	1,90	-	25,7	-	-
15	0+313	P	523/1	03.82	12,30	-	25,7	-	-
16	0+358	P	522	03.82	1,40	-	25,7	-	-
17	0+365	P	521/1	03.82	2,60	-	25,7	-	-
18	0+367	L	454	03.82	2,80	-	25,7	-	-
19	0+377	P	517/1	03.82	4,20	-	25,7	-	-
20	0+377	L	453/2	03.82	5,40	-	25,7	-	-
21	0+397	P	517/2	03.82	4,50	-	25,7	-	-
22	0+442,50	P	513	03.82	2,60	-	25,7	-	-
23	0+459	P	512	03.82	1,30	-	25,7	-	-
24	0+489	P	510	03.82	4,20	-	25,7	-	-
25	0+550	L	438/1	03.82	2,60	-	25,7	-	-
26	0+555,40	P	463	03.85	5,50	62,5	-	-	-
27	0+657	P	502	03.82	5,80	-	25,7	-	-
28	0+742,60	P	641	03.85	3,60	62,5	-	-	-
29	1+000	L	422	03.83	12,40	-	28,0	0,4	5,0
30	1+050	P	483	03.83	4,60	-	28,0	0,4	5,0
31	1+241	L	636	03.83	16,40	-	28,0	0,4	5,0
32	1+300	P	478	03.83	8,60	-	28,0	0,4	5,0
33	1+350	P	475	03.83	3,00	-	28,0	0,4	5,0
34	1+430	L	421	03.83	13,40	-	28,0	0,4	5,0
35	1+566	P	39/1;469	03.83	6,10	-	28,0	0,4	5,0
36	1+567,84	L	65	03.86	3,90	62,5	-	0,5	7,5
37	1+730	L	10	03.83	8,40	-	28,0	0,4	5,0
38	1+837,10	L	130	03.86	9,70	62,5	-	0,5	7,5
39	1+870	P	41/1	03.83	6,60	-	28,0	0,4	5,0
40	1+945	P	40/6	03.82	3,30	-	25,7	-	-
41	1+975	L	19/4	03.82	3,20	-	25,7	-	-
42	2+051	P	41/2;42/2	03.82	7,40	-	25,7	-	-
43	2+080	L	57	03.82	5,80	-	25,7	-	-
44	2+137	P	39/4	03.82	4,70	-	25,7	-	-
45	2+177	L	59	03.82	2,50	-	25,7	-	-
46	2+204	P	45/2	03.82	4,10	-	25,7	-	-

Lp	Lokalizacja	Strona	Nr działki	Typ katal. wg KPED	Objętość robót m3	Powierzch. naw. bitum. m2	Powierzch. naw. żwirow. m2	Średnica rur m	Długość rur mb
1	2	3	4	5	6	7	8,0	9	10
47	2+210	L	260	03.82	2,80	-	25,7	-	-
48	2+255	P	46/2	03.82	3,60	-	25,7	-	-
49	2+290	L	47/7	03.82	3,00	-	25,7	-	-
50	2+311	P	47/2	03.82	3,80	-	25,7	-	-
51	2+318	L	47/8	03.83	2,90	-	28,0	0,4	5,0
52	2+350	L	48/4	03.83	3,50	-	28,0	0,4	5,0
53	2+352,84	P	49/9	03.85	6,90	62,5	-	-	-
54	2+410	P	50	03.82	6,50	-	25,7	-	-
55	2+412	L	62/2	03.83	5,50	-	28,0	0,4	5,0
56	2+486,90	P	129	03.85	9,10	62,5	-	-	-
57	2+584	P	53/2;52/2	03.82	6,30	-	25,7	-	-
58	2+635	L	52/1;55/3	03.83	3,80	-	28,0	0,4	5,0
59	2+653,50	P	54/2;55/2	03.82	9,10	-	25,7	-	-
60	2+819	L	11/1;12/2	03.83	7,60	-	28,0	0,4	5,0
61	2+824	P	11/2;12/1	03.82	10,40	-	25,7	-	-
62	2+927,20	P	79	03.85	8,10	62,5	-	-	-
63	3+017,50	L	12/2;12/3	03.83	2,40	-	28,0	0,4	5,0
64	3+017,50	P	13/2	03.83	3,10	-	28,0	0,4	5,0
65	3+088,58	L	88	03.86	7,60	62,5	-	0,6	10,0
66	3+105	P	13/2;13/3	03.83	8,20	-	28,0	0,4	5,0
67	3+151	P	13/4	03.82	3,90	-	25,7	-	-
68	3+186,64	P	80	03.85	4,10	62,5	-	-	-
69	3+193	L	16/2	03.82	2,80	-	25,7	-	-
70	3+221	P	16/5	03.82	1,80	-	25,7	-	-
71	3+255	L	16/3	03.82	4,60	-	25,7	-	-
72	3+310	L	16/4;17/6	03.82	2,40	-	25,7	-	-
73	3+342	P	17/2	03.82	8,40	-	25,7	-	-
74	3+353,50	P	20/1	03.82	6,80	-	25,7	-	-
75	3+364	L	20/2	03.82	2,10	-	25,7	-	-
76	3+391	P	21/1;22/1	03.82	2,40	-	25,7	-	-
77	3+394	L	21/2	03.83	2,20	-	28,0	0,4	5,0
78	3+417	L	22/2	03.83	2,10	-	28,0	0,4	5,0
79	3+429	L	24	03.83	3,80	-	28,0	0,4	5,0
80	3+446	P	25/1	03.82	4,20	-	25,7	-	-
81	3+453	L	25/2	03.83	4,00	-	28,0	0,4	5,0
82	3+485	P	26/1;27/3	03.82	3,40	-	25,7	-	-
83	3+524	L	27/2	03.83	3,80	-	28,0	0,4	5,0
84	3+645	P	33	03.83	3,80	-	28,0	0,4	5,0
85	3+684	L	52/1;52/2	03.83	7,90	-	28,0	0,4	5,0
86	3+810	P	19/2;34/3	03.83	9,50	-	28,0	0,4	5,0
87	3+842	P	35/5;35/2	03.83	9,10	-	28,0	0,4	5,0
88	3+865,30	L	34/5	03.86	4,70	62,5	-	0,5	7,5
89	3+868,50	P	35/3;36	03.83	8,60	-	28,0	0,4	5,0
90	3+926,62	P	457	03.86	6,30	62,5	-	0,6	10,0
91	4+006	P	136/5;136/6	03.83	6,80	-	28,0	0,4	5,0
92	4+023	L	136/8	03.83	5,20	-	28,0	0,4	5,0
93	4+033,50	P	136/9	03.83	2,50	-	28,0	0,4	5,0
94	4+079	P	107/6	03.83	4,80	-	28,0	0,4	5,0
95	4+150	P	107/7	03.83	4,10	-	28,0	0,4	5,0
96	4+320,50	P	107/7;107/2	03.83	2,10	-	28,0	0,4	5,0
97	4+403	P	107/3;108/2	03.83	6,20	-	28,0	0,4	5,0
98	4+497	P	109/5	03.83	3,50	-	28,0	0,4	5,0
99	4+559,10	P	109/6	03.86	4,70	62,5	-	0,6	10,0

Lp	Lokalizacja	Strona	Nr działki	Typ katal. wg KPED	Objętość robót m3	Powierzch. naw. bitum. m2	Powierzch. naw. żwirow. m2	Średnica rur m	Długość rur mb
1	2	3	4	5	6	7	8,0	9	10
100	4+621,50	L	147/10	03.83	2,80	-	28,0	0,4	5,0
101	4+627	P	109/2	03.83	3,60	-	28,0	0,4	5,0
102	4+655	L	147/9	03.83	8,40	-	28,0	0,4	5,0
103	4+670,50	P	109/2	03.83	5,10	-	28,0	0,4	5,0
104	4+690	P	109/8	03.83	4,80	-	28,0	0,4	5,0
105	4+850	L	154/1	03.82	8,80	-	25,7	-	-
106	4+900	P	121/1	03.82	6,10	-	25,7	-	-
107	4+971,50	P	153	03.85	6,40	62,5	-	-	-
108	5+009	L	154/1	03.82	3,80	-	25,7	-	-
109	5+026,40	L	159	03.85	3,20	62,5	-	-	-
110	5+068	L	158/1;158/2	03.82	3,40	-	25,7	-	-
111	5+107	P	124	03.82	1,90	-	25,7	-	-
112	5+134	L	156/4	03.82	2,70	-	25,7	-	-
113	5+140,50	P	126/2	03.82	3,90	-	25,7	-	-
114	5+163	L	160/1	03.82	3,10	-	25,7	-	-
115	5+165,50	P	128/2	03.82	3,30	-	25,7	-	-
116	5+187	L	162/1	03.82	2,90	-	25,7	-	-
117	5+209	P	131/2	03.82	2,40	-	25,7	-	-
118	5+229	L	164/1	03.82	3,00	-	25,7	-	-
119	5+238,50	P	132/2	03.82	2,40	-	25,7	-	-
120	5+250	L	165/1	03.82	2,70	-	25,7	-	-
121	5+267	L	166	03.82	2,50	-	25,7	-	-
122	5+282	P	118/4	03.82	2,70	-	25,7	-	-
123	5+334	P	263/1	03.82	4,10	-	25,7	-	-
124	5+361	P	263/2	03.82	3,90	-	25,7	-	-
125	5+450	P	275	03.82	3,70	-	25,7	-	-
126	5+482	P	275	03.82	4,60	-	25,7	-	-
127	5+495	P	275	03.82	5,20	-	25,7	-	-
128	5+517	L	425	03.82	3,30	-	25,7	-	-
129	5+528	P	276/1	03.82	1,20	-	25,7	-	-
130	5+544	P	276/1	03.82	4,70	-	25,7	-	-
131	5+563	L	174	03.82	3,00	-	25,7	-	-
132	5+586	P	276/2	03.82	8,40	-	25,7	-	-
133	5+613	P	180	03.82	2,70	-	25,7	-	-
134	5+635	L	175/1	03.82	4,90	-	25,7	-	-
135	5+651	P	179	03.82	2,20	-	25,7	-	-
136	5+676	P	178	03.82	1,40	-	25,7	-	-
137	5+688	P	177/4	03.82	1,50	-	25,7	-	-
138	5+769	L	150/5	03.82	4,70	-	25,7	-	-
139	5+807,85	P	470	03.85	6,20	62,5	-	-	-
140	5+941	L	150/5	03.82	7,10	-	25,7	-	-
141	5+959	P	151/3;192	03.82	6,20	-	25,7	-	-
142	6+115	L	151/1;153/1	03.83	1,80	-	28,0	0,4	5,0
143	6+118	P	151/2;153/2	03.82	5,40	-	25,7	-	-
144	6+237	P	153/2	03.82	7,50	-	25,7	-	-
145	6+264	P	153/2	03.82	3,10	-	25,7	-	-
146	6+284	L	153/1;26/2	03.83	2,70	-	28,0	0,4	5,0
147	6+390	P	26/4	03.82	4,90	-	25,7	-	-
148	6+479	L	26/4	03.82	1,90	-	25,7	-	-
149	6+479	P	26/12	03.82	2,40	-	25,7	-	-
150	6+646	P	26/5;26/6	03.82	7,80	-	25,7	-	-
151	6+738	L	65/3	03.82	6,10	-	25,7	-	-
152	6+759	L	26/6	03.83	1,20	-	28,0	0,4	5,0
153	6+820	L	64/2	03.83	10,50	-	28,0	0,4	5,0

Lp	Lokalizacja	Strona	Nr działki	Typ katal. wg KPED	Objętość robót m3	Powierzch. naw. bitum. m2	Powierzch. naw. żwirow. m2	Średnica rur m	Długość rur mb
1	2	3	4	5	6	7	8,0	9	10
154	6+820	P	26/8	03.82	13,90	-	25,7	-	-
155	6+944	L	64/5	03.83	2,40	-	28,0	0,4	5,0
156	6+951,50	P	64/1	03.82	19,70	-	25,7	-	-
157	7+008	P	29/1	03.82	7,10	-	25,7	-	-
158	7+032	P	30	03.82	4,20	-	25,7	-	-
159	7+035	L	62	03.82	2,70	-	25,7	-	-
160	7+075	L	63	03.82	2,10	-	25,7	-	-
161	7+075	P	28/2	03.82	2,90	-	25,7	-	-
162	7+090	P	31/2	03.82	2,40	-	25,7	-	-
163	7+152	L	153	03.82	3,20	-	25,7	-	-
164	7+152,50	P	34	03.85	1,40	62,5	-	-	-
165	7+199,50	P	35	03.82	6,30	-	25,7	-	-
166	7+216,50	P	36/1	03.82	2,80	-	25,7	-	-
167	7+260	L	57/4	03.82	3,10	-	25,7	-	-
168	7+276	P	36/3	03.82	2,90	-	25,7	-	-
169	7+295	L	55/2	03.82	2,40	-	25,7	-	-
170	7+310	L	56	03.82	2,70	-	25,7	-	-
171	7+321,60	L	150	03.85	1,80	62,5	-	-	-
172	7+552	P	18/2	03.83	2,50	-	28,0	0,4	5,0
173	7+557,50	L	51	03.82	7,90	-	25,7	-	-
174	7+558	P	42	03.83	3,80	-	28,0	0,4	5,0
175	7+572	P	43	03.83	4,70	-	28,0	0,4	5,0
176	7+580	P	147	03.83	4,50	-	28,0	0,4	5,0
177	7+587	L	50	03.82	6,30	-	25,7	-	-
178	7+601	L	49	03.82	5,70	-	25,7	-	-
179	7+607	L	48	03.82	6,00	-	25,7	-	-
180	7+612	P	44/2;46/2	03.83	5,10	-	28,0	0,4	5,0
181	7+643	L	47	03.82	4,90	-	25,7	-	-
RAZEM					851,80	1062,50	4329,8		302,50

Rury fi 0,400 - mb 250,00

Rury fi 0,500 - mb 22,50

Rury fi 0,600 - mb 30,00

Podczas realizacji zadania lokalizacja zjazdów może ulec zmianie.